

# Addendum/correction/clarification to Eaton Stage Tender

This is a correction to the addendum released 8<sup>th</sup> August 2018 with incorrect deadline extension date.

## **Tender deadline**

Extended to 4pm, Thursday 16<sup>th</sup> August, 2018.

## **Electrical**

Wiring: AC inside and NMD for anything outside is acceptable

Service: 200Amp service. Wire size to be #3/0 AWG Cu in **1.5"** conduit. (This is a correction to the 1.25" conduit in the plans)

## **Concrete Slab**

Finish to be broom finished (not smooth).

## **Flooring**

Regular square edged treated plywood is an acceptable alternative to pressure treated T&G.

Resilient flooring refers to interior flooring.

## **Old Stage**

Will be removed by the new owner by the end of August.

Lisa Betts

Clerk Treasurer

Village of Pugwash

[lisabetts@pugwashvillage.com](mailto:lisabetts@pugwashvillage.com)